IEA HTS ExCo 2017/07/04

Present Status of Taiyo Nippon Sanso Neon Turbo-Brayton Refrigerator

Shigeru Yoshida



Contents

- About Taiyo Nippon Sanso
- NeoKelvin® -Turbo Concept
- NeoKelvin® -Turbo 2kW
- NeoKelvin® -Turbo 10kW
- TsukubaTest Facility
- User List
- NeoKelvin®-Turbo Features
- Summary



About Taiyo Nippon Sanso Corporation



Industrial gas

Electronics

Electronics



Plants & Engineering (Air separation plant etc.)



Stable isotope (Medical)



LP gas



Turbo-machinery




Cryogenic equipment



Refrigerator & Cooling System




HTS applications



Power Cable



FCL





Railroad




TNSC's Business Field in HTS Cable

TNSC will provide HTS equipment cooling service to all over the world.

- 1) NeoKelvin®-Turbo (Neon Refrigerator)
- 3) Liquid Nitrogen


- 2) Termination & Circulation System(Design and Manufacture)
- 4) Remote Monitoring






"NeoKelvin ® -Turbo" concept

- Neon gas is used as a working fluid
- Magnetic bearings are adopted in rotational machines
- Plate-fin heat exchanger is used as a sub-cooler






NeoKelvin®-Turbo 2kW




Icheon Substation Field Test

- ➤ The 2kW prototype was installed at Gochang test site in Dec. 2013, and moved to Icheon substation in 2015.
- > The total operation time in Korea is more than 8500 hours






NeoKelvin®-Turbo 10kW



NeoKelvin®-Turbo 10kW Flow diagram







Jeju Island Field Test (Energized at April 2016)



10kW Prototype Refrigerator

HTS Cable Terminals



Turbine-Compressor

- ➤ Increased pressure ratio of compressor impeller
- > Improved Motor performance
- Improved insulation structure for reducing heat-in leak




Compressor impeller



Turbine impeller








Performance of turbine of Improved TC

- ➤ Turbine efficiency was improved to 80 %
- > Over 5kW cooling power was obtained by using one Improved TC





Test Facility for NeoKelvin®-Turbo

- ➤ The new Testing House has been built in 2015
- > Turbine-compressor can be tested under cryogenic condition using test facility
- ➤ Refrigerator can be tested in Testing house with Liquid Nitrogen Circulation




Test facility for Turbine-compressor(TC) inspection








LN Circulation Unit



Refrigerator performance test flow diagram





NeoKelvin®-Turbo User List

Year	User	Type	# of sets
2013	LSC/KEPCO	2kW Prototype	1
2014	Ishikari Project	2kW Commercial type	3
2015	LSC/KEPCO	10kW Prototype	1
2015	RTRI	2kW Commercial type	1
2016	SWCC	2kW Commercial type	1
2017	KEPCO	10kW Commercial type (7.5kW spec.)	1
2018	SOX	2kW Commercial type	3



Summary

- Total operation time of 2kW prototype refrigerator is more than 8,500 hours in KOREA.
- 10kW prototype refrigerator has been operated suitably for cooling HTS cable for ten months in Jeju.
- Turbine-Compressor (TC) performance was improved to get cooling power of 10kW.
- Improved TC has been operated continuously for seven months in the test facility. Operation will be extended to 12 months.

Thank you

